

SECTION 01000
SUMMARY OF WORK:
FY12 AIR HANDLER REPLACEMENT
UNIVERSITY OF HOUSTON – CLEAR LAKE
GENERAL

1.01 Summary Of Work:

A. The work included under these specifications shall consist of furnishing all items, materials, operations, or methods listed, mentioned, indicated, or scheduled in these specifications, including all labor, materials, equipment, transportation and incidentals necessary and required for the project completion. This summary is furnished as a brief overview only and is not intended to describe all work required. The Contractor is cautioned to review all plans and specifications as well as existing jobsite conditions for the complete work

1.02 Work Included:

Air handler 26 – 21 MR Demolish only

Air handler 32 – 22 MR Demolish. Tie in ductwork and add 2 zone control units (furnished by contractor.)

Air handler 20 – Central Plant electrical vault. Demolish and replace.

Air handler 23 – 11 MR. No demolition. Replace only.

Mechanical Work

Transportation of new owner provided air handling units from the Bayou Basement to the installation locations as shown. Re-assembly as required, hanging and supporting the units, fabrication and installation of ductwork transitions, piping connections and other items as may be required to run the units effectively and efficiently. Fabrication and installation of ductwork from demolished air handler 32 into ductwork of air handler 25. Installation only of new air handler 23.

Electrical Work

Connection of units to the nearest junction box. Control wiring to existing mechanical control system is by others.

END OF SECTION
Summary of work - 01000