

Public Bid # P-2085 Summary of Bid

<u>QTY</u>	<u>UM</u>	<u>DESCRIPTION</u>
------------	-----------	--------------------

1	ea	Eaton 9390, Model 40 UPS or equal Rated 60 kVA/54 kW Input Voltage: 480 VAC, 3 phase, 60 Hz, 3 wire, and ground Battery Runtime: 50 minutes at 54 kW load
---	----	--

UPS Module (UPM)

Module input contractor
2-step battery current limit
IGBT/PWM inverter
IGBT/PWM rectifier
Module input and module output fuses
Modular assemblies
100% rated, continuous-duty static switch – wrap around
Module status/control panel w/LCD
Form-C contacts for customer interface
Bottom/top entry for cables
Input current harmonic distortion less than 4.5% @ F.L.
Single or Dual Input feed option
PXGX Ethernet SNMP Network Card
Four (4) X-Slot Communication Card Slots
UPS Dimensions: 19"W x 33"D x 74"H; 640 lbs.

Integrated Battery Cabinet (IBC-L)

QTY (2) matching battery cabinets
Provides 50 minutes @ 54 kW inverter load, 77 degrees F/25 degrees C, 1.67 ecv
Cabinet mounted circuit breaker
Dimensions: 43"W x 32"D x 74"H; 325 lbs. (each)
Power and control connections and cables are included for adjacent battery cabinets placed adjacent to UPS

Maintenance Bypass Transformer Cabinet (IDC)

3 Breaker Maintenance Bypass
QTY (2) 42 pole panelboards
480:208/120 volt transformer
35 kAIC rated
Top or bottom entry
Dimensions: 36"W x 32"D X 74"H; 1350 lbs.

Five year UPS warranty, 7x24 coverage, 8 hour response includes parts, labor, and travel
Three year Powerware battery warranty
Five year battery preventative maintenance (2 visits per year)
Freight to jobsite loading dock
Onsite start-up service in Eaton Field Service (7x24)

NOTE: THIS DOCUMENT IS FOR INFORMATIONAL PURPOSES ONLY. THIS IS NOT AN OFFICIAL SOLICITATION DOCUMENT

NOTE: THIS DOCUMENT IS FOR INFORMATIONAL PURPOSES ONLY. THIS IS NOT AN OFFICIAL SOLICIATION DOCUMENT